

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 12/14/82
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API NUMBER 15-065-21,200-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR PETROLEUM MANAGEMENT, INC. OPERATORS LICENSE NO. 5242

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208 PHONE # (316) 686-7287

LEASE (FARM NAME) Lappin WELL NO. 1

WELL LOCATION NW NE NW SEC. 1 TWP. 6 S RGE. 21 ~~XXX~~(W)

COUNTY Graham TOTAL DEPTH 3612 FIELD NAME _____

check one:
OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain) (Ks. Drillers Log-1980)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN March 21, 1983 1:00 P.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wayne Fuzzell ADDRESS P. O. Box H, Plainville, KS 67663

PHONE # (913) 434-2042

PLUGGING CONTRACTOR Barlow Well Service LICENSE NO. 987

ADDRESS P. O. Box 868 Great Bend, KS 67530 PHONE # (316) 792-6759

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208 PHONE # (316) 686-7287

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OR ACTING AGENT.

RECEIVED
STATE CORPORATION COMMISSION

3-15-83
MAR 15 1983

SIGNED: Wade S. Siefert
(Applicant or Acting Agent)

DATE: 3/10/83

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

15-065-21200-00-00

OPERATOR: Petroleum Management Inc.

WELL NAME: Lappin #1 LOCATION: NW NE NW 1-6S-21W

COUNTY: Graham STATE: Kansas

WELL COMMENCED: February 20, 1980 WELL COMPLETED: February 27, 1980

ELEVATION: 2196' G.L. TOTAL DEPTH: 3612'

PRODUCTION: Oil RIG NO: #2

CASING - 8-5/8": 192.17' of 28# cemented with 125 sxs common 2% gel 3% cc

4 1/2" ~~XXXXXX~~ 3611' of 9.5# cemented with 100 sxs H.L.C., 150 sxs 50-50 poz

2% gel 8% salt 83 JTS. plug down @ 7:15 P.M.

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	201'	sand	201' - 1/2 degree	
201'	360'	cement and shale		
360'	1460'	shale and sand		
1460'	1929'		1522' - 1/2 degree	
1735'	1774'	Anhydrite		
1929'	2330'	shale		
2330'	2399'	shale and sand	2399' - 1 1/2 degrees	
2399'	2475'	shale and lime		
2475'	2770'	shale and lime		
2770'	2935'	shale and lime		
2935'	3073'	shale and lime		
3073'	3222'			
3222'	3293'	lime and shale		
3293'	3293'			
3293'	3351'	shale and lime		
3351'	3418'	lime and shale		
3418'	3418'	lime and shale		
3418'	3465'	lime and shale		
3465'	3465'	lime and shale		
3465'	3552'	lime and shale		
3552'	3612'	shale and lime and sand and granite		
3612'	RTD			

STATE OF KANSAS
COUNTY OF


The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct

PIONEER DRILLING CO., INC.

By Raymond J. Lomen

SUBSCRIBED AND SWORN TO, BEFORE ME, This 7th day of May, 1980.

Connie Jo Austin
NOTARY PUBLIC



RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1983

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



15-069-21200-00-00

JOHN CARLIN
C. LOUX
JANE T. ROY
WILLIAM R. DICK
RICHARD RIGGS

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202

March 22, 1983

WELL PLUGGING AUTHORITY

Lappin #1
NW NE NW, Sec. 1-6S-21W
Graham
T.D. 3612'
Barlow Well Service

Petroleum Management, Inc.
400 North Woodlawn
Ste. 201
Wichita, KS. 67208

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,

Carol J. Larson, Administrator

KCC-KDHE, Dist., #6, 1014 Cody, Hays, KS., 67601, (913)628-1200
is hereby assigned to supervise the plugging of the above named well