

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-065-03331-0000

WELL PLUGGING APPLICATION FORM

Well Location C SE NE NE Sec. 1 Twp. 6 Rge. (E) 21 (W)

Field Name (if any) Ray County Graham

Lease (Farm Name) Hixenbaugh Well No. 1

Was well log filed with application? yes If not, explain circumstances and give available data (Use an additional sheet if necessary)

Date and hour plugging is desired to begin March 4, 1941

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desires (Use an additional sheet if necessary)

PLUGGING
FILE SEC L-16-R2116
BOOK PAGE 32 LINE 14

Name of the person on the lease in charge of well for owner

G. F. Hulse Address Stockton, Kansas

Name of well owner or Acting Agent Cetal Oil Company

Address 1015 Central Building, Wichita, Kansas 3-26-41

Invoice covering assessment for plugging this well should be sent to:

Cetal Oil Company Address 1015 Central Building, Wichita, Kansas

and payment will be guaranteed by applicant.

CETAL OIL COMPANY

BY: [Signature]
Operator or Acting Agent

Date 3-24-41

Hixenbaugh well No. 1
 E/2 NE/4 1-6S-21W, Graham County, Kansas

CETAL OIL COMPANY

IS-065-03331-00-00

FORMATION	FROM	TO
Surface Clay	0	110
Shale & Shells	110	1050
Sand	1050	1100
Shale	1100	1200
Sand	1200	1380
Lime	1380	1425
Red Rock	1425	1525
Red Bed	1525	1650
Anhydrite	1650	1695
Shale & Shells	1695	1760
Broken Lime	1760	1920
Lime	1920	2015
Shale & Shells	2015	2170
Lime	2170	2200
Shale	2200	2250
Shale & Lime	2250	2380
Shale & Shells	2380	2545
Shale	2545	2590
Lime	2590	2625
Lime & Shale	2625	2830
Shale & Shells	2830	2950
Lime & Shale	2950	3120
Lime	3120	3226
Shale	3226	3238
Lime	3238	3488
Shale	3488	3520
Shale & Lime	3520	3536
Correction	3536 =	3534
Granite Wash	3534	3538
Granite	3538	3540

Started rigging up rotary 1-9-41
 Tearing out rotary tools 1-23-41

Moved in Drilling In Unit 1-28-41
 Tearing out Cable tools 2-1-41

Surface casing: Ran 6 joints 112'2" of 8 5/8" O.D. 8 thd.
 casing set at 103' with 100 sacks cement.

Ran 113 joints casing (12 joints 332'11" of 5 9/16" O.D.
 casing, and 101 joints of 18# 5 1/2" 8 thd. O.D. casing 3213'1")
 3546' over all, set at 3529'6" with 100 sacks cement.

MAR 28 1941
 STATE CORP. COMM.
 CONSERV. DIV.
 326-41

PLUGGING
 FILE REC. 1-6-R-21W
 BOOK PAGE 130 LINE 14



15-065-03331-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

March 6, 1941

IN REPLY PLEASE
REFER TO THIS
SUBJECT

Well No. 1
Farm Hixonbaugh
Description C SE NE NE 1-6-21W
County Graham
File 150-14

Harbar Drilling Co.
1015 Central Bldg.
Wichita, Kansas

Dear Sirs:

This letter is your permit to plug
the above subject well, in accordance
with the Rules and Regulations of the
STATE CORPORATION COMMISSION.

Yours very truly,

STATE CORPORATION COMMISSION

T. A. MORGAN, DIRECTOR
CONSERVATION DIVISION

HA

BY: J. P. Roberts
J. P. ROBERTS

NOTICE: C. T. Alexander
Great Bend, Kansas