

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01579-00-01
Spot: SESWSW Sec/Twnshp/Rge: 35-9S-23W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: DIEBOLT Well #: 4
County: GRAHAM Total Vertical Depth: 3953 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: P.O. BOX 20380
WICHITA, KS 67208

PROD Size: 7 feet: 3951
SURF Size: 10 feet: 215

128⁴⁷

Well Type: EOR UIC Docket No: E26988.2 Date/Time to Plug: 03/09/2005 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CURT GABEL Company: BEREN CORPORATION Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 330 sxs 60/40 pozmix - 10% gel - 800# hulls - 33 sxs gel.
Squeezed at 1700' w/205 sxs cement.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/09/2005 2:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Annulus full of cement.
TIH with tubing to 3860' and spotted 75 sxs common 3% cc with 400# hulls.
Let cement set up.
RIH and tagged TOC.
Pulled tubing up to 3550' - mixed and pumped 33 sxs gel spacer.
Pulled up to 1400' and circulated cement with 165 sxs cement with 400# hulls.
POOH and topped with 20 sxs cement.

RECEIVED
MAR 16 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

Form CP-2/3

MAR 10 2005

DATE 3-16-05
NO. 2005061291

