

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22914-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 22-11S-16W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: GLICK Well #: 1
County: ELLIS Total Vertical Depth: 3410 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

PROD Size: 4.5 feet: 3378 135 SX CMT
SURF Size: 8.625 feet: 217 135 SX CMT

110⁸³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2005 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: TED FUCHS Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 175 sxs Swift Multi-Density Cement and 500# hulls.
Dakota 181'-481'. Anhy 944'-984'. Salt 1299'-1529'.
Fluid level 1347'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2005 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech shot two hole perfs at 525' and 975' - stacked up in oily bridge at 1347' - shot hole.
Swift rigged to 4 1/2" casing with a swedge.
Pumped 135 sxs SMD cement with 500# hulls mixed in.
Max. P.S.I. 800#. S.I.P. 400#.
Rigged to 8 5/8" casing and pumped one sack SMD cement.
Max. P.S.I. 1000#.
Blew small hole in weld on casing.
No shut in pressure.

Perfs:

Top	Bot	Thru	Comments
3301	3307		
3126	3140		

RECEIVED
MAR 17 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #772.

Plugged through: CSG

District: 04

Signed *Pat Staab*
(TECHNICIAN)

INVOICED

DATE 3-18-05

INV. NO. 2005061298

MAR 11 2005

LIBERTY ENTERPRISES INC

308 W MILL
PLAINVILLE, KS 67663

#1 GLICK


22-11-16W
NW NW SE

CONTR PIONEER DRILLING CO

CTY ELLIS

GEOL _____

FIELD CHRISLER



ELV 1786 KB SPD 4/30/82 CARD ISSUED 10/14/82

IP P 25 BOPD, NW

1787 GL

PENN-CGL 3301-3307
(NEW PAY)

API 15-051-22,914

SMP	Top	Depth/Datum
ANH	944 + 842
TOP	2706 - 920
HEEB	2945 - 1159
TOR	2971 - 1185
LANS	2996 - 1210
BKC	3235 - 1449
ARB	3380 - 1594
PENN-CGL	NA
TD	3410 - 1624

8 5/8 " 217/135SX, 4 1/2 " 3378.35/150SX
NO DST'S
MICT - CO, PF (PENN-CGL) 3301-3307, W / 4 SPF, AC 750 G
(MA), TSTD, POP, P 25 BOPD, NW, 6/1/82

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

WICHITA
WICHITA
WICHITA