

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01770-00-00
Spot: NWSESW Sec/Twnshp/Rge: 32-9S-20W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: TUCKER Well #: 2
County: ROOKS Total Vertical Depth: 3818 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

PROD Size: 5.5 feet: 3813
SURF Size: 8.625 feet: 201

124⁰⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2005 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 265 sxs Swift Multi-Density Cement and 600# hulls.
Dakota 738'-1038'. Anhy 1748'-1788'. Salt 2106'-2193'.
Fluid level 2000'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2005 3:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech RIH and perfed at 1050' - 1775' - 2225'.
Swift Services rigged to 5 1/2" casing with a swedge.
Pumped 238 sxs Swift Multi-Density cement with 600# hulls mixed in to circulate cement to surface out of 8 5/8" casing.
Shut in 8 5/8" casing and pumped 27 sxs SMD cement.
Max. P.S.I. 200#. S.I.P.0#.
Will top off well if needed.

Perfs:

Top	Bot	Thru	Comments
3813	3818	OH	

RECEIVED
MAR 17 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #773.

Plugged through: CSG

District: 04

Signed: [Signature]
(TECHNICIAN)

INVOICED

DATE 3-18-05

INV. NO. 2005061298

MAR 11 2005

KAISER-FRANCIS

#2 TUCKER

32-9-20W

NW SE SW

Contr. H-30, INC

ROOKS County

E.2243 RB Comm.

Comp. 5-8-59

IP

180 BOPD

Tops	Depth	Datum
ANH	1748	+495
HEEB	3467	-1224
TOR	3490	-1247
LANS	3508	-1265
B/KC	3733	-1490
CHRTY CONG	3777	-1534
SIMP SH	3788	-1545
SIMP SND	3793	-1550
ARB	3807	-1564
TD	3818	-1575

Casing
 8" 201
 5" 3813
 DST 3530-90/1 HR, 1890' FR O, NW, BHP 920//
 DST 3630-3710/1 HR, 205' M, SSO, BHP 910//
 DST 3812-18/1 HR, 1370' O, 130' W, BHP 860//

CO TD: FU 800' FLD/30", FU 2400' FLD: BL 5
 GW & 23 GO: FU 2570' FLD/4 HR

COOPER POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS