

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-09082-00-01  
Spot: SESESE Sec/Twnshp/Rge: 16-9S-18W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: PARADISE CREEK Well #: 101  
County: ROOKS Total Vertical Depth: 3569 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

PROD Size: 5.5 feet: 3566 150 SX CMT  
SURF Size: 8.625 feet: 1485 750 SX CMT

# 115<sup>99</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2005 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel with 600# hulls - 17 sxs gel.  
Perf casing at 850'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/09/2005 2:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 3400' - spotted 17 sxs gel, followed with 50 sxs cement with 300# hulls.  
Pulled tubing to 1500' - spotted 130 sxs cement with 300# hulls to circulate cement to surface.  
POOH with tubing - pumped down 5 1/2" casing with 40 sxs cement.  
Max. P.S.I. 700#. No circulation out of 8 5/8".  
Hooked up to 8 5/8" S.P. Pressured up to 500#. Broke down.  
Hooked back up to 5 1/2" casing.  
Squeezed 80 sxs cement with good circulation of H-20 out of 8 5/8".  
Called for more cement. Waited one hour.  
Pumped additional 20 sxs cement down 5 1/2" casing.  
Circulated cement to surface out of 8 5/8" S.P.  
Pressured up casing to S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3566	3569		
3316	3496		

RECEIVED  
MAR 17 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Dennis L. Hamel  
(TECHNICIAN)

INVOICED

DATE 3-18-05

INV. NO. 2005061303

MAR 14 2005

15-163-09087-00-01  
16-9-18W  
SE SE SE

CITIES SERVICE OIL CO. #1 KABA (OWWO)

Contr. \_\_\_\_\_ ROOKS County

E 2154 Comm. \_\_\_\_\_ Comp. 8/11/66 IP PMP 112 BO + 182 RWP  
(KC 3472-96)

Tops	Depth	Datum	Casing
			8" 1485
			5" 3566
HEEB	3262	-1108	WAS; SAME OPR, IPP 615 BOPD/PHY POT, 12/19/47;
DODGE	3289	-1135	FU 625' 0/12 HRS; PMP 31 BO + 1 1/2 BW/7 HRS; A 250; SWB LD;
LANS	3309	-1155	NEW INFO: ARB DECLINED TO 5 BOPD + 363 BW; PB 3550; PF 10/3472-77;
			6/3487-90; 6/3493-96; A 3000; POP;
			PMP 120 BO + 23 BW; REC LD; PMP 140 BO + 35 BW/24 HRS; TOOK OFF PMP;
ARB	3565	-1411	10/3402-07; 10/3413-18; BP 3440; A 2000; POP; PMP 30 BO + 49 BW/18 HRS;
			PARADISE CREEK PMP 60 BO + 116 RWPD
			PMP 44 BO + 69 RWPD; PMP 80 BO + 130 BWPD;
TD	3569	-1415	

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

11/10/66  
 STAG  
 WADICER