

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-21, 952-00-00

SW, Sec. 28, T 6 S, R 17 W E

990 feet from S section line

990 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8290

Lease Name Main Well # 1

Operator: S & M Oil
Name & Address 2004 Vine, Hays, Ks. 67601

County Rosks.
Well Total Depth 3440 feet 111.80

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 621

Address P.O. Box 506, Russell, Ks. 67665

Company to plug at: Hour: 10:00 AM Day: 11 Month: 2 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Joe Brannon

(company name) Emphasis Oil Operations (phone) 913-483-5345

were: Order 180 sh. 50% pozmix - 4% Gel. - 3% Cal. Cl. & 8 5/8" plug.
Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C
3440' w/ 20 sh. 2nd plug C 1300' w/ 20 sh. 3rd plug C 800' w/ 80 sh.
4th plug C 300' w/ 40 sh. 5th plug: solid bridge of shells & plug C 40'
w/ 10 sh. Circulate 10 sh. in rat hole.

Signed Guth Li Schel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:00 PM Day: 11 Month: 2 Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 248' S.P. conc. w/ 150 sh. common - 2% Gel. - 3% Cal. Cl.

Ordered 180 sh. 50% pozmix - 4% Gel. - 3% Cal. Cl. & 8 5/8" plug. Spot w/ drill
stem w/ heavy mud between all plugs. 1st plug C 3440' w/ 20 sh.
2nd plug C 1300' w/ 20 sh. 3rd plug C 800' w/ 80 sh. 4th plug C
300' w/ 40 sh. 5th plug: solid bridge of shells & plug C 40' w/ 10 sh.
Circulated 10 sh. in rat hole.

Remarks: Dulled in Arbuckle.

RECEIVED
STATE CORPORATION COMMISSION
MAR 4 1983
CONSERVATION DIVISION
Wichita, Kansas
3-14-83

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ did not) observe this plugging.

INVOICED

DATE 3-30-83

INV. NO. 3801-W

Signed Guth Li Schel
(TECHNICIAN)