

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23035-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 20-8S-22W  
1650 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: WHITE TRUST Well #: 2-20  
County: GRAHAM Total Vertical Depth: 3700 feet

Operator License No.: 3293  
Op Name: RUSSELL OIL, INC.  
Address: P.O. BOX 1469  
PLAINFIELD, IL 60544

SURF Size: 8.625 feet: 217

\$ 120<sup>25</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/13/2005 9:00 PM  
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC  
Proposal Rcvd. from: BURT BEERY Company: RUSSELL OIL, INC. Phone: (785) 735-4637

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE  
Date/Time Plugging Completed: 03/13/2005 11:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Perfs:

No ar buckle cut.  
1st. Plug at 1800' w/25 sxs.  
2nd. Plug at 1003' w/100 sxs.  
3rd. Plug at 267' w/40 sxs.  
4th. Plug at 40' w/10 sxs.

RECEIVED  
MAR 17 2005  
KCC WICHITA

Remarks: ACID SERVICES, INC.

Plugged through: DP

District: 04

Signed

Bruce D. Basye  
(TECHNICIAN)

INVOICED

DATE

3-18-05

INV. NO.

2005061302

Form CP-2/3

MAR 14 2005