

15-163-00116-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging off formations.

Rooks County, Sec. 32 Twp. 6 Rge. (E) 17 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines N SE SE SE
Lease Owner Westgate-Greenland Oil Company
Lease Name Behrens Well No. 1
Office Address 1022 Union National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed October 16, 1948 19
Application for plugging filed October 16, 1948 19
Application for plugging approved October 16, 1948 19
Plugging commenced October 16, 1948 19
Plugging completed October 16, 1948 19
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 3347 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
surface		0	354	10 3/4"	354	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3347 to 250'
Halliburton plug with 20 sacks cement
Filled from there to 20' with heavy mud
Halliburton plug at 20' with 10 sacks cement
Filled to cellar base

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to G. E. Bitler, Westgate-Greenland Oil Company
Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler
1022 Union National Bank Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of October, 1948

Esther Russell
Notary Public.

My commission expires May 25, 1948

PLUGGING
FILE SEC 32 T 6 R 17W
BOOK PAGE 62 LINE 27

10-2348

COMPANY: Westgate Greenland Oil Company
 CONTRACTOR: Jackson Drilling Corporation
 FARM: Behrens #1
 LOCATION: SE SE SE Section 32-6-17W
 Rooks County, Kansas
 ELEVATION: 1843
 COMMENCED: October 2, 1948
 COMPLETED: October 15, 1948

0	to	40	Gravel & shale
40	to	260	Shale
260	to	480	Shale & lime
480	to	730	Puritic shale
730	to	935	Sand
935	to	965	Shale
965	to	1085	Shale & red bed
1085	to	1238	Red bed
1238	to	1270	Anhydrite
1270	to	1275	Shale & salt shells
1275	to	1865	Shale & shells
1865	to	2475	Lime & shale
2475	to	2560	Shale
2560	to	2730	Lime & shale
2730	to	2795	Lime
2795	to	2905	Lime & shale
2905	to	3278	Lime
3278	to	3297	Shale
3297	to	3347	Lime
		3347 T.D.	

10 3/4" surface casing set at 354 feet. Cemented with 200 sacks cement
 Top - Arbuckle - 3295
 Dry and abandoned

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Behrens #1, Rooks County, Kansas, Section 32-6-17W, as reflected by files of the Jackson Drilling Corporation.

Clare A. Stewart
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas this 20th day of October, 1948

Dorothy J. Wilson
 Dorothy J. Wilson

My Commission expires November 30, 1950

PLUGGING
 FILE SEC 32 T 6 R 17W
 BOOK PAGE 162 LINE 27

23 348
 10-23-48