

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Cla-Mar Oil Company  
Address: P.O. Box 1197, Hays, Kansas 67601  
Phone: (785) 625-3863 Operator License #: 6509  
Type of Well: D&A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 12/28/05 (Date)  
by: Hays (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

API Number: 15-051-25395-0000  
Lease Name: York/Hadley  
Well Number: 4  
Spot Location (QQQQ): \_\_\_\_\_ - S/2 - NE - SW  
1600 Feet from  North /  South Section Line  
3450 Feet from  East /  West Section Line  
Sec. 32 Twp. 11 S. R. 17  East  West  
County: Ellis  
Date Well Completed: 2-28-2005  
Plugging Commenced: 2-28-2005  
Plugging Completed: 2-28-2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	219'	8 5/8"	219'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged with 225 sacks 60/40 Poz., 6% Gel., 1/4# flocele per sack. 1st. plug - 25 sacks @ 3650', 2nd. plug - 25 sacks @ 1345', 3rd. plug - 100 sacks @ 790', 4th. plug - 40 sacks @ 260', wiper plug - 10 sacks @ 40' to surface, rat hole - 15 sacks, mouse hole - 10 sacks.

Name of Plugging Contractor: Vorfeld Drilling, Inc.  
Allied Cementing Company, Inc. License #: 9431  
Address: P.O. Box 31, Russell, Kansas 67665  
Name of Party Responsible for Plugging Fees: \_\_\_\_\_  
State of \_\_\_\_\_ County, \_\_\_\_\_, ss.

RECEIVED  
MAR 18 2005  
KCC WICHITA  
*KCC Ben 3-18-05 RBDms CP 73*

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) P.O. Box 1197 Hays KS 67601

SUBSCRIBED and SWORN TO before me this 16th day of March, 2005  
LINDA L. DEWEY  
Notary Public - State of Kansas  
My Appt. Expires 10/1/08  
[Signature] Notary Public  
My Commission Expires: 10/1/08

*BW*