

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2070
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

API NUMBER 15-065-23,027-0000

LEASE NAME Rice Trust D

WELL NUMBER #1-8

940 Ft. from S Section Line

390 Ft. from ^W Section Line

SEC. 8 TWP. 8S ROR. 22 (R) or (W)

COUNTY Graham

Date Well Completed 3-6-05

Plugging Commenced 3-6-05

Plugging Completed 3-6-05

TYPE OR PRINT
NOTICE: Fill out completely
and return to Comm. Div.
office within 30 days.

LEASE OPERATOR Russell Oil, Inc.

ADDRESS PO Box 1469, Plainfield, Illinois 60544

PHONE (815) 609-7000 OPERATORS LICENSE NO. 3,293

Character of Well D & A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-5-05

by Herb Deines

(KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	217'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Push bridge plug to 1,775', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 925', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 275', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor SHIELDS DRILLING CO.

License No. 5184

Address Shields Bldg., Russell, KS 67665

RECEIVED

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Russell Oil, Inc.

MAR 17 2005

STATE OF KANSAS

COUNTY OF RUSSELL

KCC WICHITA

Jack P. Beeman, Sec.-Treas

Contractor


(Employee of ~~XXXXXX~~) or ~~XXXXXXXXXX~~
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 10th day of March, 2005

My Commission Expires:



Quin Phillips
Notary Public

Ben