

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20083-06-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1969
CONSERVATION DIVISION
Wichita, Kansas
10-31-69

Operator's Full Name National Associated Petroleum Company

Complete Address: Triangle Bldg., Pawhuska, Oklahoma 74056

Lease Name Geo Duncan Well No. 1

Location SE SE NW Sec. 32 Twp. 6 Rge. (E) (W) 17

County Rooks Total Depth 3366'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 12:15P Day 29 Month 10 Year 1969

The Above well was plugged as follows:

Total Depth 3366' 8 5/8 csg set at 208' cwc

5 1/2 csg set at 3366' cw 100 sk cmt.

5 1/2 csg PBTB 3155' and perf. (3147-3152)

5 1/2 csg DV tool set at 1267' and GWC to surface.

No pipe recovered.

Pumped thru 5 1/2 plug container with 20 sk gel W/4 sk hulls, plug and 70 sk 50-50 poz

cmt W/6% total gel. Max pres 400 lbs. SI pres 400 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/31/69

INV. NO. 755-4

Signed: Geo F. Massey
Well Plugging Supervisor