

KANSAS

4
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-00116-06-01

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1970
CONSERVATION DIVISION
Wichita, Kansas
1-6-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Armstrong-Jackman & Aspen

Complete Address 915 Century Plaza Bldg., Wichita, Kansas 67202

Lease Name Wagner Well No. 1

Location SE SE SE Sec. 32 Twp. 6 Rge. (E) (W) 17

County Rooks Total Depth 3572'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Inc.

Address Box 221 Great Bend, Kansas License No. 637 637

Operation Completed: Hour 11A Day 3 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 3572' 10 3/4 csg set at 354' cwc 250 sk.

5 1/2 csg set at 3302' cw 200 sk cmt.

5 1/2 csg PBTB 3281' with top perf. (2962)

Filled 5 1/2 csg W/sd (2940-3281) Dumped 5 sk cmt W/dump bailer. (2900-2940)

Cutoff and recovered 2105' of 5 1/2 csg.

Pumped down 10 3/4 csg with 50 sk baroid and 35 sk gel and 180 sk 60-40 cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1-6-70
INV. NO. 1213-W

Signed: Geo A. Massey
Well Plugging Supervisor