

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-30179-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

10-31-69
RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Associated Petroleum Company

Complete Address: Triangle Bldg., Pawhuska, Oklahoma 74056

Lease Name Nettie Riffel Et al Well No. 1

Location SE NE Sec. 31 Twp. 6 Rge. (E) (W) 17

County Rooks Total Depth 3302

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 10:30A Day 29 Month 10 Year 1969

The Above well was plugged as follows:

Total Depth 3302' 8 5/8 csg set at 182' cwc

5 1/2 csg set at 3222' cw 100 sk cmt.

5 1/2 csg PBTD 3184 with perf. (3064-3168)

Filled 5 1/2 csg W/sd (3050-3184) Dumped 5 sk cmt W/dump bailer. (3010-3050)

Butt off and recovered 2460' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 15 sk gel W/4 sk hulls, plug and 130 sk 50550 poz
cmt W/6% total gel. Max. pres. 300 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/31/69

INV. NO. 754-W