

DISTRICT CONSERVATION AGENT'S REPORT

15-163-00477-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW SE

SEC. 7 TWP. 6 RGE. 17W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Kemmler

Operator Lewis Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3406 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 165' circulated with cement - 5 1/2" at 3377' with
175 sax cement behind.

Lane Wells plugs to 3232' - top perforations at 3218'.

Filled with sand to 3200', set 4 sax cement with dump

bailer, pulled 2600' 5 1/2" - filled hole with mud to 165',

set rock bridge and 15 sax cement, mud to 35', set rock and

10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1952
CONSERVATION DIVISION
Wichita, Kansas

J. P. [Signature]
District Conservation Agent
Date 5-27-52

PLUGGING
FILE SEC 7 TWP 6 R 17W
BOOK PAGE 19 LINE 29

5-29-52