

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-163-20540-00

SEP 13 1974  
09-13-1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Zenith Drilling Corporation,

Complete Address Suite 600, 200 West Douglas, Wichita, Kansas.

Lease Name Hamit Well No. 1

Location NE-SE-SE Sec. 20 Twp. 6 Rge. (E) (W) 19

County Rooks Total Depth 3612'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Ks. License No.       

Operation Completed: Hour 1:15 PM Day 10 Month 9 Year 1974

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft. cement  
thru DP from 975' to 650'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru DP  
from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: R. L. Dinkel  
Well Plugging Supervisor

INVOICED

DATE 9/13/74  
INV. NO. 9878-W