

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1972
08-17-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20454-00-00

Operator's Full Name John O. Farmer, Inc.
Complete Address 370 W. Wichita Ave. Russell, Kansas 67665
Lease Name Brobst Well No. 2
Location C SE SW Sec. 8 Twp. 6 Rge. (E) (W) 19
County Rooks Total Depth 3695'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 2 A Day 14 Month 8 Year 1972

The above well was plugged as follows:

RTD 3695' 8 5/8 csg set at 203' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Messing
Well Plugging Supervisor

DATE 8/21/72
INV. NO. 6200-W