

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

OCT 10 1972  
10-10-1972  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-20435-00-00

Operator's Full Name Oklahoma Fracturing Services, Inc.

Complete Address 630 United Founders Life Tower  
5900 Mosteller Drive Oklahoma City, Oklahoma 73112

Lease Name Brobst BROBST Well No. 1

Location C NE SE Sec. 7 Twp. 6 Rge. (E) (W) 19

County Rooks Total Depth 3615'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 12:45 P Day 4 Month 10 Year 1972

The above well was plugged as follows:

Total Depth 3615' 8 5/8 csg set at 202' cwc 150 sk. Cmt. Mat. 50-50 poz W/6% gel.

5 1/2 csg set at 3611' cw 125 sk cmt.

Filled 5 1/2 csg W/sd (3590-3615) Dumped 5 sk cmt W/dump bailer. (3555-3590)

Cutoff and recovered 1500' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/500 lbs hulls, - 70 sk cmt - 7 sk

gel & water - released 8 5/8 plug and pumped 50 sk cmt by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 10/11/72

INV. NO. 6434-10