

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD #4
K.A.R.-82-3-117

API NUMBER 15-065-22,544 0000

LEASE NAME Holmquist

WELL NUMBER 1-11

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

380 Ft. from S Section Line

4140 Ft. from E Section Line

SEC. 11 TWP. 6S RGE. 21W (E) or (W)

COUNTY Graham

LEASE OPERATOR Perry Petroleum, Inc.

ADDRESS P.O. Box 580, Huthinson, KS 67504

PHONE # (316) 662-4401 OPERATORS LICENSE NO. 6761

Date Well Completed 11-22-89

Character of Well D & A

Plugging Commenced 11-22-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-22-89

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Herb Deines, Hays

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3790

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8-5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

1st plug @ 1885' w/ 20 sx 15 sx in rat hole
2nd plug @ 1115' w/100 sx 10 sx in mouse hole
3rd plug @ 300' w/40 sx
4th plug @ 40' w/10 sx

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack E. Goss (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack E. Goss

(Address) Jack E. Goss, Agent for Operator
250 N. Water, Suite 300
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 4th day of December, 19 89

Melanie Rau
Melanie Rau Notary Public



My Commission Expires: 4-18-93

15-065-22544-00-00

DRILLER'S WELL LOG

PERRY PETROLEUM, INC.
HOLMQUIST #1-11
Graham County, Kansas.

COMMENCED: November 16, 1989
COMPLETED: November 22, 1989

0' - 1615' Sand & Shale
1615' - 1865' Shale & Shells
1865' - 1900' Anhydrite
1900' - 1925' Shale
1925' - 2860' Lime & Shale
2860' - 3450' Shale & Lime
3450' - 3790' Lime & Shale
3790' RTD

Surface Casing: Set 6 jts. 8-5/8"
at 261' with 165 sacks 60/40
Pozmix, 2% gel, 3% cc.


AFFIDAVIT


STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

James B. Phillips, of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.


James B. Phillips

Subscribed and sworn to me this 15th day of December, 1989.




Sally R. Byers Notary Public