

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2028
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22374-00-00

LEASE NAME Holmquist-Lagerberg

WELL NUMBER 3

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 11 TWP. 06 RGE. 21 (W)

COUNTY GRAHAM

Date Well Completed 6-17-87

Plugging Commenced 11-5-02

Plugging Completed 11-5-02

RECEIVED
NOV 19 2002
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 14201 E Central Wichita, KS 67230

PHONE# (316) 733-4798 OPERATORS LICENSE NO. 5242

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-5-02 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? -

Producing Formation Arbuckle Depth to Top 3718 Bottom 3741 T.O. 3785

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	386	0
				4-1/2	3784	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:

Ran tubing to 1900' Pumped 25 SX 60-40 Poz + 10% gel Followed by 85 SX 60-40 Poz + 10% Gel + 400# Cotton Seed Hulls. Pulled Tubing. Pump 100 SX 60-40 Poz + 10% Gel down casing - Pressure to 100 PSIG - Shut-IN. Pump 5 SX 60-40 Poz + 10% Gel down 4-1/2 - 8-5/8 Annulus Pressure To 500 PSIG. Shut-IN.

Name of Plugging Contractor PLAINS, Inc License No. 4072

Address P.O. Box 346 Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc

STATE OF KANSAS COUNTY OF Sedgwick, ss.

GARY L. Reed As Agent (Employer of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Gary L. Reed

(Address) 14200 Brookline Ct. Wichita, KS 67230

SUBSCRIBED AND SWORN TO before me this 18 day of November, 2002

Jacquie D Sanders
Notary Public

My Commission Expires: JAN 19 2003



OR