

STATE OF KANSAS
STATE CORPORATION COMMISSION
200' Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,535
LEASE NAME Beecher

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
~~2310~~ ²⁹⁷⁰ Ft. from S Section Line
~~3760~~ ¹⁵²⁰ Ft. from E Section Line

LEASE OPERATOR Ritchie Exploration, Inc.
ADDRESS 125 N. Market, Suite 1000, Wichita
PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767
Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SEC. 9 TWP. 6 RGE. 21W(E)or(W)
COUNTY Graham
Date Well Completed 10-89
Plugging Commenced 8-11-94
Plugging Completed 8-11-94

The plugging proposal was approved on August 15, 1994 (date)
by David Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____
Producing Formation L/KC, Toronto Depth to Top 3337' Bottom 3530 T.D. 3710

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	220	-0-
				4 1/2	3690	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pressured 8 5/8" to 300#, held. Plugged 4 1/2 csq w/165 sxs 60/40 poz, 10% gel & 300# hulls. Max pump pressure 1000#. Shut in at 500#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____
Address _____


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.
STATE OF Kansas COUNTY OF Sedgwick, ss.

Ritchie Exploration, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 125 N. Market, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 26th day of August, 19 94

My Commission Expires:



Notary Public

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1994
CONSERVATIVE DIVISION
WICHITA, KANSAS