

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-065-22,425-00-00

LEASE NAME Boys

WELL NUMBER 1

2970 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 8 TWP. 6S RGE. 21 ~~XXXX~~ (W)

COUNTY Graham

Date Well Completed 11-25-87

Plugging Commenced 11-26-87

Plugging Completed 11-26-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Jerry Patterson Oil Company

ADDRESS Box 307 Logan, S 67646

PHONE#(913) 4897 OPERATORS LICENSE NO. 9559

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist #6 Hays, KS Dale Bolthazor State Plugger

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Sent to operator to complete

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

1st plug from 3670' to 3570' w/25 sx; pumped mud to 1860'; 2nd plug from 1860' to 1760' w/25 25 sx; pumped mud to 1070'; 3rd plug from 1070' to 670' w/100 sx; pumped mud to 310'; 4th plug from 310' to 150' w/40 sx; pumped mud to 40' and solid bridge; 5th plug from 40' to surface w/10 sx. Pumped 10 sx in rathole. All cement 60/40 posmix w/6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422



Address 801 Union Center Wichita, KS 67202 12-10-87

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as if I had that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 87

Notary Commission Expires: 12-29-90

Janet A. Stuck
 Notary Public