

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL RECORDS  
K.A.R.-82-3-117

API NUMBER 15-065-21,913 ~~00-00~~

LEASE NAME Desbien "A"

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2310 Ft. from S Section Line

2970  
330 Ft. from E Section Line

SEC. 13 TWP. 6 S RGE. 21 XXX or (W)

COUNTY Graham

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 14201 East Central Wichita, Ks. 67230

PHONE 316 ) 733-5600 OPERATORS LICENSE NO. 5242

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 5-18-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-20-98

The plugging proposal was approved on 5-18-98 (date)

by District 4 (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation LKC Depth to Top 3564' Bottom 3663' T.D. 3860'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD read 6-2-98

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	379'	275'
				4 1/2"	3784'	1230'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Sanded to 3490'. Bailed 4 sks cement. Shot at 1230'. Spotted 60 sks with 350# huls. Pulled to 300' and circulated cement to surface with 85 sks and 150# huls. Pulled the rest of the pipe. Hole stayed full.

Name of Plugging Contractor Quality Well Service Inc. License No. 31925

Address 249 Beth Drive Sterling, Ks. 67579-9048

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Gary L. Reed Agent

(Signature of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Gary L. Reed

(Address) 14201 E. Central Wichita, Kansas 67230



AND SWORN TO before me this 29 day of May, 19 98

Dana R. Clothier  
Notary Public

My Commission Expires: 11-13-2000

USE ONLY ONE SIDE OF EACH FORM