

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,911-00-00

LEASE NAME MORRIS

WELL NUMBER #1

4290 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 12 TWP. 6 RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 1/5/84

Plugging Commenced 10/5/94

Plugging Completed 10/5/94

#4
TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 14201 E. Central, Wichita, KS 67230

PHONE#(316) 733-5600 OPERATORS LICENSE NO. 5242

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 16, 1994 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation KC Depth to Top 3259 Bottom 3451 T.D. 3522

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	369'	0
				4 1/2	3521'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Ran 2" tbg to 2360' & spot 100 sx cement with 200# hulls. Pulled up to 1200'. Circulated cement to surface with 50 sx & 100# hulls. Came out with tbg. Hooked up to 4 1/2" csg & squeezed in 75 sxs @ 700# max psi. Shut in @ 350#. 8 5/8" backside mixed 50 sxs @ 600# max. Shut in @ 400#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. D. Reber (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. D. Reber

(Address) 14201 E. Central, Wichita, KS 67230

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 94

My Commission Expires:



Kathleen L. Carter
Notary Public