

RECEIVED

10-11-2002
2002

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API # 15-065-22374 ⁻⁰⁰⁻⁰⁰ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Petroleum Management, Inc. KCC LICENSE # 5242
(owner/company name) (operator's)

ADDRESS 14201 East Central CITY Wichita

STATE Kansas ZIP CODE 67230 CONTACT PHONE #(316) 733-5600

LEASE Holmquist -Lagerberg WELL# 3 SEC. 11 T. 06S R. 21 (xxxx/West)

- SE - SW - SE SPOT LOCATION/QQQQ COUNTY Graham

330 FEET (in exact footage) FROM S/x (circle one) LINE OF SECTION (NOT Lease Line)

1650 FEET (in exact footage) FROM E/x (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL x GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8 SET AT 386' CEMENTED WITH 220 SACKS

PRODUCTION CASING SIZE 4-1/2 SET AT 3784' CEMENTED WITH 100 SACKS
DV set @ 1882' cemented with 365 sacks.

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3718-3741'

ELEVATION 2225 KB T.D. 3785' PBTD 3768' ANHYDRITE DEPTH 1865'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD x POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Pump 40 sx 60/40 POZ + 10% gel w/ 3 sx hulls, 10 sx gel spacer, 105 sx 60-40 POZ to surface. Test 8-5/8 - 4-1/2 annulus, if not cemented surface, pump 25 sx 60/40 POZ w/ 2 sx hulls.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES
(LOG filed with previous application)
If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

GARY L. REED PHONE# (316) 733-4798

ADDRESS 14200 BROOKLINE CT. City/State WICHITA, KANSAS 67230

PLUGGING CONTRACTOR Allied Cementing Co., Inc. KCC LICENSE # 99994
(company name) (contractor's)

ADDRESS PO BOX 31 Russell, KS 67665-0031 PHONE # (785) 483-2627

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) As Soon as possible

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR XXXXXXXX

DATE: 10/9/02 AUTHORIZED OPERATOR/AGENT: Gary Reed
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Petroleum Management, Inc.
14201 East Central
Wichita, KS 67230-1515

October 15, 2002

Re: HOLMQUIST-LAGERBERG #3
API 15-065-22374-00-00
SESWSE 11-6S-21W, 330 FSL 1650 FEL
GRAHAM COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor