

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-065-22,321-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Davis Petroleum, Inc. OPERATORS LICENSE NO. 4656

ADDRESS RR 1 Box 183-B Great Bend, KS 67530 PHONE # (316) 793-3051

LEASE (FARM) Beecher WELL NO. 1-9 WELL LOCATION SW NE SE COUNTY Graham

SEC. 9 TWP. 6 RGE. 21 (S) or (W) TOTAL DEPTH 3675' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 371' CEMENTED WITH 190 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? operator to be filed by
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 9-2-86 6:20 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leonard Williamson PHONE # (316) 793-8366

ADDRESS Box 823 Great Bend, KS 67530 STATE CORPORATION COMMISSION

PLUGGING CONTRACTOR Duke Drilling Co., Inc. CONSERVATION DIVISION LICENSE NO. 5929
Wichita, Kansas

ADDRESS Box 823 Great Bend, KS 67530 PHONE # (316) 793-8366

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Leonard Williamson
(Operator or Agent)

DATE: 9-2-86

15-065-22321-00-00

DRILLER'S WELL LOG

DATE COMMENCED: August 27, 1986
DATE COMPLETED: September 2, 1986

Davis Petroleum, Inc.
BEECHER #1-9
SW NE SE
Sec. 9, T6S, R21W
Graham County, Ks.

ELEVATION: 2174 K.B.

0 - 1821' Surface Soil, Sand, Shale, Red Bed
1821 - 1859' Anhydrite
1859 - 3150' Lime & Shale
3150 - 3186' Lime
3186 - 3195' Sand & Shale
3195 - 3384' Lime
3384 - 3407' Shale & lime
3407 - 3610' Lime
3610 - 3675' Shale, Lime, Chert, Sand
3675' RTD

FORMATION DATA

Anhydrite 1821'
Howard 3150'
Severy 3186'
Topeka 3195'
Heebner 3384'
Toronto 3407'
Kansas City 3423'
Base K.C. 3610'
Conglomerate 3624'
RTD 3675'

Surface Pipe: Set new
8-5/8", 20# pipe @371'
w/190 sacks 60/40 pozmix
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 4th day of September 1986.

Dorothy M. Hague
Notary Public



SEP - 5 1986
CONSERVATION DIVISION
Wichita, Kansas