

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-065-22,425 - 0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Jerry Patterson Oil Company OPERATORS LICENSE NO. 9559

ADDRESS Box 307 Logan, KS 67646 PHONE # (913) 689-4897

LEASE (FARM) Boys WELL NO. 1 WELL LOCATION SW NE NW COUNTY Graham

SEC. 8 TWP. 6S RGE. 21 ~~(E) (W)~~ TOTAL DEPTH 3740 PLUG BACK TO _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 273 CEMENTED WITH 190 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug at 3670' w/25 sx; 2nd plug at 1860'
w/25 sx; 3rd plug at 1070' w/100 sx; 4th plug at 310' w/40 sx; 5th plug at 40' w/10 sx. 10 sx
in rathole. All cement 60/40 posmix 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No
(If not, explain) Sent to operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8:00 p.m. 11-25-87

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: _____

Harold Maley

PHONE # (913) 674-5768

ADDRESS 216 E. McFarland Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 801 Union Center Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: December 9, 1987

12-10-87
RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1987
CONSERVATION DIVISION
Wichita, Kansas