

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE COPY)

4398
RECEIVED
KANSAS CORP
APR - 3 11:45

API # 15-065-21, 913 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Petroleum Management, Inc. (owner/company name) KCC LICENSE # 5242 (operator's)

ADDRESS 14201 East Central CITY Wichita

STATE Kansas ZIP CODE 67230 CONTACT PHONE #(316) 733-5600

LEASE DESBIEN "A" WELL# 1 SEC. 13 -T06S -R.21 (xxxx/West)

NE - NE - SE SPOT LOCATION/0000 COUNTY GRAHAM

2310 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2970 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8 SET AT 379 CEMENTED WITH 275 SACKS

PRODUCTION CASING SIZE 4-1/2 SET AT 3784 CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGE PLUG SETS: 3564-67; 3586-90; 3648-49; 3655-63
BRIDGE PLUG @ 3788

ELEVATION 2268 KB T.D. 3860 PBSD 3788 ANHYDRITE DEPTH 1872
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING SAND BACK TO 3550'. SET 50' CEMENT PLUG. SHOOT PIPE, PULL TO 1902' (BASE ANHD). IF FREEPOINT IS ABOVE ANHYDRITE, SHOOT CASING BELOW ANHDRITE AND SQUEEZE PER KCC REQUIREMENTS. PLUG COMING OUT OF HOLE PER KCC.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? YES

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DON KEENER PHONE# (785) 434-2042

ADDRESS P.O. BOX H City/State PLAINVILLE, KS 67663

PLUGGING CONTRACTOR UNKNOWN Quality Well Service KCC LICENSE # 31925 (contractor's)

ADDRESS PHONE #

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) AS WEATHER PERMITS

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR XXXXXXXX

DATE: 4/1/98 AUTHORIZED OPERATOR/AGENT: [Signature] (signature)

4



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

April 9, 1998

Petroleum Management Inc
14201 East Central
Wichita KS 67230

Desbien "A" #1
API 15-065-21,913 -00-00
2310 FSL 330 FEL
Sec. 13-06S-21W
Graham County

Dear Don Keener,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #4
2301 E 13th
Hays KS 67601
(913) 628-1200