

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

API Number 15 - 163 - 21060-00-00 (of this well)  
Lease Owner Cinco Exploration Company  
Address P. O. Box 3723, Victoria, Texas 77901  
Lease (Farm Name) ODLE Well No. 1  
Well Location C NW NE Sec. 34 Twp. 6S Rge. 19W (E)        (W)         
County Rooks Total Depth 3600' Field Name         
Oil Well        Gas Well        Input Well        SWD Well        Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin 12:30 a.m., 4-28-80

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:  
Bill Craig Address 702 S. 2nd Street, Hill City, KS

Plugging Contractor Abercrombie Drilling, Inc. License No.         
Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:  
Name Cinco Exploration Company  
Address P. O. Box 3723, Victoria, Texas 77901

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 16 1980  
05-16-1980  
CONSERVATION DIVISION  
Wichita, Kansas

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge  
Applicant or Acting Agent  
Jack L. Partridge, Asst. Sec.-Treas.  
Date: May 14, 1980

RECEIVED  
 CONSERVATION COMMISSION  
 MAY 16 1980  
 CONSERVATION DIVISION  
 Wichita, Kansas

CONTRACTOR'S WELL LOG

15-163-21060-00-00

OPERATOR: Cinco Exploration Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: ODLE #1  
 LOCATION: C NW NE, Section 34-6S-19W,  
 Rooks County, Kansas  
 SPUD DATE: 4-21-80  
 COMPLETION DATE: 4-28-80

0	262	Shale & Sand
262	725	Shale
725	1575	Shale & Sand
1575	2430	Shale
2430	3200	Lime & Shale
3200	3600	Lime
	3600	Rotary Total Depth

Spud hole at 6:45 p.m., 4-21-80. Drilled 262' of 12-1/4" hole. Ran 6 joints of 8-5/8" used 28# casing. (Tally 253.44). Set at 261'. Cemented with 200 sacks of Class A Cement, 2% gel, 3% Ca.Cl. Cement did circulate. Plug was down at 12:30 a.m., 4-22-80.

T.D. 3600'. Set 1st plug at 870' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, and rathole with 5 sacks. Job complete at 12:30 a.m., 4-28-80.

SAMPLE TOPS:

Anhydrite 1570'  
 B/Anhydrite 1617'

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the ODLE #1, C NW NE, Section 34-6S-19W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 14th day of May, 1980.

Sherrie L. Brooks  
 Sherrie L. Brooks



State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
WILLIAM G. GRAY

Governor  
Chairman  
Commissioner  
Commissioner

Carol J. Larson, Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

May 1, 1980

15-163-21060-00-00

WELL PLUGGING AUTHORITY

Odle Well No. 1  
NW NE, Sec. 34-6S-19W  
Rooks County  
3600'  
Abercrombie Drlg., Inc.


Cinco Exploration, Company  
3935 Hartsdale  
Houston, TX 77063

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) day from the above date.

Yours very truly,

  
J. LEWIS BROCK, Administrator

Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, KS 67601  
is hereby assigned to supervise the plugging of the above named well