

4 060035

11-22

218R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,544-0000  
50'N&150'E  
SE SW SW, SEC. 11, T 6 S, R 21 W/E  
380 feet from S section line  
4140 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6761  
Operator: Perry Petroleum, Inc.  
Name & Address: P.O. Box 580  
Hutchinson, KS 67504

Lease Name Holmquist Well # 1-11  
County Graham 123.17  
Well Total Depth 3790 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXXXXXXX  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 6033  
Address Wichita, KS

Company to plug at: Hour: 7:00PM Day: 22 Month: November Year: 19 89

Plugging proposal received from Lloyd Dellett  
(company name) Murfin Drlg. Co. (phone) 316-267-3241

were: Space all plugs through drill pipe with heavy drilling mud.  
Order 195 sxs. 60/40 pos 6% gel 1/4# floccel per sx.

Arbuckle not reached

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXXX

Operations Completed: Hour: 7:00PM Day: 22 Month: November Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1885' with 20 sxs. Anhydrite 1865-1900  
2nd plug at 1115' with 100 sxs. Dakota 814-1114'  
3rd plug at 300' with 40 sxs. Surface pipe to 261  
4th plug at 40' with 10 sxs.

RECEIVED

STATE CORPORATION COMMISSION  
3-8-90  
MAR 08 1990

Remarks: Applied Cementing  
Kathole with 15 sxs. mouse hole with 10 sxs.

(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby authorize to serve this plugging.

DATE 3-16-90  
INV. NO. 27696

Signed Herb Deines  
(TECHNICIAN)

Herb Deines