

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22374-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 11-6S-21W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: HOLMQUIST-LAGERBERG Well Number: 3  
County: GRAHAM Total Vertical Depth: 3785 feet

Operator License No.: 5242  
Op Name: PETROLEUM MANAGEMENT, INC.  
Address: 14201 EAST CENTRAL  
WICHITA, KS 67230

Conductor Pipe: Size feet: \$123.01  
Surface Casing: Size 8.625 feet: 386 220 sx  
Production: Size 4.5 feet: 3784 100 sx  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/05/2002 8:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: GARY L REED Company: PETROLEUM MANAGEMENT, INC. Phone: (316) 733-4798

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 400# hulls.  
W.H.M. - 3650'.  
D.V. at 1882' - circulate at surface with 365 sxs cement.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/05/2002 9:00 AM

KCC Agent: DENNIS HAMEL

**Actual Plugging Report:**

R.I.H. with tubing to 1850'.  
Spotted 110 sxs cement with 400# hulls. Circulated at surface.  
POOH with tubing and squeezed 4 1/2" casing with 100 sxs cement.  
Max. P.S.I. 500#. S.I.P. 200#.  
Rigged up cementers to 8 5/8" S.P. Pressured up to 500#.  
Job complete.

RECEIVED  
DEC 03 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE 12-3-02

INV. NO. 2003060900

Form CP-2/3

DEC 02 2002

replacement card

UNOICED

PETROLEUM MANAGEMENT, INC.  
WICHITA, KS. 67208

11-06 -21W  
SE SW SE

#3 HOLMQUIST-LAGERBERG

site: 10 N & 1/2 W OF NICODEMUS, KS.

city: GRAHAM

API 15-065-22374

contr: RED TIGER DRILLING

field: WC (PIONEER NE DISO)

geol: BILL PETERSEN

fr date 05/12/87    spd date 05/18/87    drlg comp 05/26/87    card issued 09/30/87    last revised 12/28/88


ELV: 2235	KB LOG
tops.....	depth/datum
B/FT HAYS .....	436 +1799
FAIRPORT .....	619 +1616
DAK SD .....	896 +1339
PERM.....	1590 +645
SC .....	1865 +370
B/SC .....	1895 +340
FT RILEY.....	2444 -209
WREF .....	2564 -329
NEVA .....	2774 -539
RED E .....	2840 -605
FOR .....	2878 -643
WAB .....	2967 -732
TARK .....	3130 -895

IP status:

OIL, P 20 BO & 60 BWPD, ARB 3718-3736	
TOP.....	3237 -1002
DR CR .....	3293 -1058
LECOMP.....	3360 -1125
OREAD .....	3397 -1162
HEEB .....	3443 -1208
TOR .....	3467 -1232
LANS .....	3486 -1251
KC .....	3545 -1310
BKC .....	3670 -1435
MARM .....	3695 -1460
ARB .....	3708 -1473
PBTD .....	3768 -1533

COPYRIGHT 1988  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

PETROLEUM MANAGEMENT, INC.  
WICHITA, KS. 67208

11-06 -21W  
SE SW SE

#3 HOLMQUIST-LAGERBERG

RTD..... 3785 -1550  
LTD..... 3786 -1551

CORRECTION: 12/28/88 - CORRECTED WELL SPOT BACK TO ORIGINAL  
NOTE: CORRECTION: 5/22/87 - WELL LOC CHGD IN ERROR TO C S/2 SE SE; INFO RELEASED:  
11/2/88 - WAS OIL WELL - TIGHT HOLE  
CSG: 8-5/8" 386 / 220 SX, 4-1/2" 3784 / 100 SX  
NO CORES

DST (1) 3388-3408 (OREAD), / 45-45-45-45, (1ST OP) FB, (2ND OP) FB, REC 125' W ISIP 928#  
FSIP 870# IFF 35# -58# FFP 70# -81#

DST (2) 3610-3656 (KC), / 30-30-15-30, (1ST OP) WB, DIED / 5", (2ND OP) NB, REC 5' DM ISIP  
58# FSIP 46# IFF 46# -46# FFP 46# -46#

DST (3) 3664-3718 (KC, MARM), / 30-30-30-30, (1ST OP) WB, DIED / 18", (2ND OP) NB, REC 10'  
SLI OCM, W / FREE OIL IN TOP OF TOOL ISIP 93# FSIP 93# IFF 46# -46# FFP 46# -46#

DST (4) 3719-3731 (ARB), / 60-45-60-45, (1ST OP) VWB INCR TO 1-1/2 INCH, (2ND OP) VWB INCR  
TO 2 INCH; 60' GIP; REC 60' MO (65% OIL, 35% M) ISIP 1054# FSIP 1009# IFF 35# -46# FFP  
46# -58#

MICT - CO, PF (ARB) 3718-3728, AC 250 GAL (7-1/2% MCA), SO, RE-AC 750 GAL (15% DS/FE),  
SO, RE-PF (ARB) 3718-3736, SO, NAT, SET 2-3/8" TBG AT 3700, NO PKR, POP, P 20 BO & 60  
BWPD, 6/26/87