

4-041604

8-16

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,535 ⁻⁰⁰⁰⁰
130'E.of

SE SW NE /4 SEC. 09 , 06 S , 21 W
~~2370~~ 2370 feet from N section line
1520 feet from W section line

Operator license# 4767 Lease Beecher well # 1

Operator: Ritchie Exploration, Inc. County Graham

Address: 125 N. Market Well total depth 3710 feet
Suite #1000 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67204 Surface pipe 8 5/8 Inch @ 220 feet
w/180 sxs.

120.58

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 16 Month: August Year: 94

Plugging proposal received from: Pete Fiuerinni

Company: Ritchie Exploration, Inc. Phone:

Were: 4 1/2" casing set @ 3690' w/125 sxs. cmt. Perfs. @ 3337'- 3530'.
Anhy. @ 1825' - W.L.M. @ 3500'.
Ordered 175 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 11:00A.M., Day: 16, Month: August, Year: 94

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped 165 sxs.
60/40 pozmix - 10% gel with 300# hulls. Max. 1000#. S.I.P. 500#.
8 5/8" pressured-up to 300#. Cement at surface.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

RECEIVED
STATE CORPORATION COMMISSION
8-31-94
AUG 31 1994

I did X] and not [] observe the plugging.

Dennis L. Hamel
HO.

(agent)
Form CP-2/3

INVOICED

DATE 9-8-94
INV. NO. 41158