

6 070208

API NUMBER 15-065-22, 023-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW-SW-SW, SEC. 8, T. 6 S, R. 21 W

330 feet from S/E section line

4950 feet from S/E section line

Lease Name CARL BOYS Well # "A"-1

County GRAHAM

Well Total Depth 3785 123.01 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 263

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Operator: A. SCOTT RITCHIE

Name & Address 125 NORTH MARKET #950

WICHITA, KANSAS
67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated TAG # 604

Plugging Contractor MURFIN DRILLING Co License Number 6033

Address WICHITA, KANS. 67202

Company to plug at: Hour: 2:00 AM Day: 3 RD Month: AUG Year: 19 84

Plugging proposal received from LLOYD DELLETT.

(company name) MURFIN DRILLING CO (phone) 316-267-4375

were: 8 5/8" - 263 #1 SP. CUL #1/200 SK Common GEL - CACEL - BY ALLIED CNT.

ORDER 220 SK 50/50 Pozmix GEL - CACEL - 1 SK #10 CELE - AND 8 5/8" PLUG

SPOT WITH DRILL STEM, TURN HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS.

NO CIRCULATION PROBLEMS, ELY. 2206 - Dnh. 1863 AIRBUCKLE

@ 3764 #

Plugging Proposal Received by Maurice Schmidt
BOK (TECHNICIAN)

Plugging Operations attended by Agent? All Part None

Operations Completed: Hour: 2:45 Day: 6 TH Month: Aug Year: 19 84

ACTUAL PLUGGING REPORT

ORDERED - 220 SK 50/50 Pozmix GEL - CACEL - 1 SK #10 CELE AND 8 5/8" PLUG

Spotted with Drill Stem - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

1st Plug @ 3715 FT #1/25 SK CNT 2nd Plug @ 1890 FT #1/25 SK CNT

3rd Plug @ 1110 FT #1/100 SK CNT + 1 SK #10 CELE, 4th Plug @ 270 FT #1/50 SK CNT

5th Plug 50/50 BRIDGE Hall's Plug @ 46 FT #1/10 SK CNT, 10 SK Rat Hdg (CEN)

Remarks: (Commented By Allied CNT)

INVOICED

If additional description is necessary, use BACK of this form.

DATE 8-16-84

INV. NO. 3151

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1984
8-13-84
CONSERVATION DIVISION
Wichita, Kansas

Signed Maurice Schmidt
BOK (TECHNICIAN)