

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-21948-00-00

NE, Sec. 15, T 6 S, R 21 (W)

2170 feet from N/2 section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Lease Name Eva Desbrien Well # 1

Operator: Petroleum Maint. Inc.
Name & Address 400 N. Woodlawn Dr
Suite 201
Wichita Ks.
67208

County Graham

Well Total Depth 3848 feet 125.06

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 375

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drlg. License Number 5302

Address 1720 Ks. State Bldg. Wichita Ks.

Company to plug at: Hour: 2 PM Day: 14 Month: 3 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Sam Wagoner

(company name) Red Tiger Drlg. (phone) 913-625-7966

were: order 210 sx cement 50/50 pozmix 6% gel.

15x hulls. 1. 8 5/8 plug 15x Flow Seal.

Heavy mud between all plugs.

Pump cement down drill pipe

Elev. 2273 Anhydrite 1916-51 Arbucklo. 3808

Dakota 1400

873 = 1175

Signed Ralf J. Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 PM Day: 14 Month: 3 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3800 for 45 mi.

25 SX @ 3800

25 SX @ 1920

100 SX @ 1175 mixed with 15x Flow Seal

40 SX @ 400 15x hulls pushed plug to 40'

10 SX @ 40

10 SX in Rat hole.

Remarks:

Cementing Co. Halliburton

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1984
CONSERVATION DIVISION
Wichita, Kansas
3-26-84

I hereby certify that the above plugging instructions were given as herein stated and that I (did did not) observe this plugging.

Signed Ralf J. Balthazor
(TECHNICIAN)

INVOICED
DATE 3-29-84
INV. NO. 0980
3-14