

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22375-00-00
Spot: CSEENENW Sec/Twnshp/Rge: 14-6S-21W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: HOLMQUIST-LAGERBERG Well Number: 4
County: GRAHAM Total Vertical Depth: 3782 feet

Operator License No.: 31569 Conductor Pipe: Size feet: #122.92
Op Name: BACH, JASON DBA BACH OIL PRODUCT Surface Casing: Size 8.625 feet: 260 220 sxs cmt
Address: RR 1, BOX 28 Production: Size 5.5 feet: 3781 100 sxs cmt
PHILLIPSBURG, KS 67661 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/05/2002 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GARY L. REED Company: JASON BACH Phone: (316) 733-4798

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 500# hulls.
Run tubing.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/05/2002 1:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 1850'.
Spotted 160 sxs cement with 400# hulls.
Circulated cement to surface.
POOH with tubing and squeezed an additional 150 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Rigged up cementers to 8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 100#.

RECEIVED
DEC 03 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Dennis J. Hamel
(TECHNICIAN)

DEC 02 2002

INVOICED Form CP-2/3
DATE 12-3-02
INV. NO. 2003060894

replacement card

PETROLEUM MANAGEMENT, INC.
WICHITA, KS. 67208

14-06 -21W
SE NE NW

#4 HOLMQUIST-LAGERBERG

site: 9-3/4 N & 1/2 W OF NICODEMUS, KS.

city: GRAHAM

API 15-065-22375

contr: RED TIGER DRILLING

field: PIONEER NE EXT (1/4 SW)

gso: BILL PETERSEN

fr date 05/12/87

spd date 06/10/87

drig comp 06/18/87

card issued 10/28/87

last revised 12/07/88

ELV: 2269 KB LOG	
tops.....	depth/datum
B/FT HAYS.....	488 +1781
ANH.....	1906 +363
B/ANH.....	1936 +333
WINF.....	2426 -157
FT RILEY.....	2483 -214
WREF.....	2604 -335
CO GR.....	2626 -357
NEVA.....	2810 -541
ADM.....	2964 -695
PENN.....	3004 -735
TARK.....	3166 -897
TOP.....	3272 -1003
LECOMP.....	3391 -1122

IP status:

OIL, P 50 BO & 50 BWPD, LKC 3658-3674 OA,	
OREAD.....	3428 -1159
HEEB.....	3476 -1207
TOR.....	3500 -1231
DOUG.....	3510 -1241
LANS.....	3516 -1247
KC.....	3578 -1309
BKC.....	3705 -1436
MARM.....	3730 -1461
PENN CONG.....	3749 -1480
ARB.....	3774 -1505
PRE CAMB.....	3780 -1511
RTD.....	3782 -1513
LTD.....	3786 -1517

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

PETROLEUM MANAGEMENT, INC.
WICHITA, KS. 67208

14-06 -21W
SE NE NW

#4 HOLMQUIST-LAGERBERG

INFO RELEASED: 12/7/88 - WAS OIL WELL - TIGHT HOLE
 CSG: 8-5/8" 260 / 220 SX, 5-1/2" 3781 / 485 SX
 NO CORES
 DST (1) 3559-3578 (LKC), / 45-45-45-45, (1ST OP) SB OFF BTM OF BKT / 3", (2ND OP) SB OFF BTM OF BKT / 4", REC 1405' SW ISIP 1123# FSIP 1112# IFP 222# -594# FFP 664# -825#
 DST (2) 3577-3614 (LKC), / 45-45-45-45, (1ST OP) WB, DIED & THEN CAME BACK & BLEW 1/4 INCH IN BKT, (2ND OP) NB, REC 61' DM, W / TR OIL ISIP 1205# FSIP 1173# IFP 74# -74# FFP 74# -74#
 DST (3) 3643-3680 (LKC), / 30-30-30-30, (1ST OP) STDY BLO INCRG TO OFF BTM OF BKT / 18", (2ND OP) STDY BLO INCRG TO OFF BTM OF BKT / 14", 270' GIP, REC 40' CLEAN GSY OIL, 310' GSY MCO (GR 41) ISIP 1180# FSIP 1135# IFP 70# -105# FFP 129# -164#
 MICT - CO, PF (LKC) 3658-3766 & 3670-3674, AC 500 GAL (15% MCA), SO, RE-AC 1500 GAL (15% SGA), GSO, SET 2-3/8" TBG AT 3750, NO PKR, POP, P 50 BO & 50 BWPD, 10/4/87