

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

. API Well Number: 15-065-22816-00-00
Spot: SESWNE Sec/Twnshp/Rge: 13-6S-21W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: BARBER Well Number: 1
County: GRAHAM Total Vertical Depth: 3837 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 200
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 04/06/2001 12:00 PM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: BILL WINN Company: MURFIN DRILLING CO., INC. Phone: (785) 650-9623

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix with 6% gel and 1/4# flocele per sack.
Spot all plugs through drill pipe with heavy mud between all plugs.

124.70

Plugging Proposal Received By: PAT STAAB

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 04/07/2001 5:15 AM

KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 3767' w/25 sxs.
2nd. Plug at 1860' w/25 sxs.
3rd. Plug at 1130' w/100 sxs.
4th. Plug at 270' w/40 sxs.
5th. Plug at 40' w/10 sxs and 8 5/8" wiper plug.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED
DATE 4-11-01
INV. NO. 2001061613

RECEIVED
STATE CORPORATION COMMISSION

APR 11 2001
4-11-2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Pat Staab

(TECHNICIAN)