

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15065 - 21,988 - 00-00
SW NW SE, Sec. 13, T 6 S, R 21 (W/4)
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242
Operator: Petroleum Management, Inc.
Name & 400 N. Woodlawn
Address Suite 201
Wichita, Ks. 67208

Lease Name Desbien Well # 2
County Graham
Well Total Depth 3852 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 379

125.19

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033 Rig Tag # 604

Address _____

Company to plug at: Hour: PM Day: 22 Month: May Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Lloyd Dellett

(company name) Murfin Drilling Comapny (phone) _____

were: Order 210 lbs. 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Signed Gilbert P. Leiker
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None ~~_____~~

Operations Completed: Hour: 4:15 AM Day: 23 Month: May Year: 19 84

ACTUAL PLUGGING REPORT

- 1st plug @ 3820 w/25 sks
- 2nd plug @ 1920 w/25 sks
- 3rd plug @ 1100 w/100 sks w/1 sk flo-cel
- 4th plug @ 400 w/40 sks
- 5th plug @ 40 w/8 5/8" plug 1/2 sk hull 10 sks cmt.
- 10 sks in Rat Hole

Remarks: Cemented by Halliburton

Partially witnessed by Dale Balthazor.

RECEIVED
STATE CORPORATION COMMISSION
5-29-84
MAY 29 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did) did not) observe this plugging.

INVOICED

DATE 6-1-84
INV. NO. 1992
5-23

Signed Gilbert P. Leiker
(TECHNICIAN)