

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 300 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-065-22,443 -00-00  
 LEASE NAME Scott 14-29

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1  
740' Ft. from S Section Line  
4680' Ft. from E Section Line  
 SEC. 29 TWP. 6S RGE. 21 ~~XX~~ or (W)  
 COUNTY Graham  
 Date Well Completed 3-16-88  
 Plugging Commenced 3-16-88  
 Plugging Completed 3-16-88

EASE OPERATOR PanCanadian Petroleum Company  
 ADDRESS 600 17th St. 1800 So. Tower Denver, CO 80202

PHONE#( 303 825-8371 OPERATORS LICENSE NO. 8000  
 Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. 6 Hays, Ks. State plugger Gilbert Balthazor

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3795'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	309'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

1st plug from 1900' to 1800' w/25sx pump mud to 1150'; 2nd plug from 1150' to 710' w/110sx pump mud to 320'; 3rd plug from 320' to 160' w/40sx pump mud to 40', 4th plug from 40' to surface w/10sx w/wiper plug. Rathole 15sx; 60-40 posmix; 6% gel; 3%cc; 1sx flocc.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422


Address 801 Union Center Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton  
 (Address) 801 Union Center, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 19 88



Janet A. Stuck Notary Public

My Commission Expires: 12-29-90

