

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-065-21572-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Petroleum Management, Inc.

Complete Address 400 N. Woodlawn - Suite 201 - Wichita - 67208

Lease Name Lappin Well No. 2

Location SE-NE-SW Sec. 1 Twp. 6 Rge. 21 (East) (West)

County Graham Total Depth 3599

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling

Address 1720 KSB Bldg - Wichita, 67208 License No. _____

Operation Completed: Hour: 1:15pm Day: 19 Month: 3 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8 set @ 220' w/165 sx common 2% gel - 3% CPD (Halliburton)
Ordered 130 sx pozmix 4% gel - 3% CPD + 8 5/8" plug
Spotted 70 sx @ 950' -> 40 sx @ 910' -> 10 sx on solid
bridge at 40'-0" -> 10 sx in Rat Hole - Circ. heavy
mud between all plugs!
(Cmt by Halliburton)

Amount of Surface Casing: 220'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Muddy road conditions!

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1982
CONSERVATION DIVISION
Wichita Kansas

Signed: Dennis L. Hamel
Conservation Division Agent

INVOICED
DATE 3-30-82
INV. NO. 9830-W