

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

15-065-02878-00-00

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 62-28

LOCATION NW NW NW

SEC. 1 TWP. 6 RGE. 21 *W*

Dry Hole          Abandoned Oil Well   x   Abandoned Gas Well         

I have this date completed supervision of plugging of:

Well No. 1 Lease Lappin

Operator W. L. Hartman Address Box 54 Wichita, Kans

Field          County Graham

Total Depth 3585 Feet.

Plugging Contractor R & S Pipe Pulling Co

Plugging Contractor's License No. 1

Address         

(Describe briefly the manner in which the well was plugged)

8 5/8" at 180' circulated with cement - 5 1/2" 3580' with 50 sax  
cement behind - Perforated at 3392'

Filled with sand to 3380', set 4 sax cement with dump bailer,  
pulled 1100' 5 1/2" - mudded to 180', set rock and 15 sax cement,  
mud to 35', set rock and 10 sax cement to bottom cellar.

**PLUGGING**  
FILE SEC 1 T 6 R 21  
BOOK PAGE 62 LINE 28

WICHITA, KANSAS  
DISTRICT CONSERVATION AGENT

*[Signature]*  
District Conservation Agent

Date 10-15-54

10-21-54