

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-163-21, 774/00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name HENNY BROWN ENTERPRISES K/C #5537

Complete Address DRAWER 340 PLAINVILLE, MO. 67663

Lease Name OSMEYER Well No. "C" #1

Location 660' F.S.L. - 660' F.E.L. - SE Sec. 31 Twp. 6 Rge. 19 (East)(West)

County ROOS Total Depth 3264 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated K/C #535

Plugging Contractor BREILING OIL INC - (MERL ROGERS)

Address R.R. I VICTORIA, MO. License No. _____

Operation Completed: Hour: 1:00 AM Day: 7th Month: OCT Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 175 FT SP. CUC. w/ 130ST COMMON - 2% GEL. - 3% CA-CL. (HALLIBURTON)
ORDERED 170ST 50/50 PORMIX 6% GEL. 3% CA-CL. AND 8 5/8" PLUG.
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1ST PLUG. @ 930 FT w/ 100ST CMT.
2ND PLUG. @ 240 FT w/ 40ST CMT.
3RD PLUG. → SOLID BRIDGE HULL'S - PLUG @ 40 FT/50 w/ 10ST CMT.
10ST IN RAT HOLE (CIRCULATE)
10ST IN MOUSE HOLE. (CIRCULATE)

Amount of Surface Casing: 175 FT (CEMENTED BY HALLIBURTON)

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Marvin Schmidt
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1982
10-19-1982
CONSERVATION DIVISION Signed: _____
Wichita, Kansas

Conservation Division Agent

INVOICED

DATE 11-9-82

INV. NO. 1533-w