

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-02623-00-00

R

File No. 42-25 County: Rooks

Location: SE NW SW Sec. 31 Twp. 6 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3583

I have this date completed supervision of plugging of:

Lease Name: Ostmeyer Well No. 21 *KCC 210 3-24-01*

Operator's Full Name: Bennett & Roberts

Complete Address: Russell, Kans

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 14 Month 6 Year 59

The above well was plugged as follows:

8 5/8" 195' circulated with cement - 5 1/2" 3579' with 150 sax cement.

PB to 3260', perforated 3247'

Filled with sand to 3230', set 4 sax cement with dump bailer, pulled

2411' 5 1/2" to 600', circulated hole with heavy mud (Gel) through 5 1/2"

displaced 20 sax cement through 5 1/2" at 600', heavy mud to 160',

displaced 20 sax cement through 5 1/2" at 160', heavy mud to 35', set

bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: *Jewel M. Ogden*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 31 T. 6 R. 19W
BOOK PAGE 42 LINE 25

JUN 17 1959
06-17-1959
CONSERVATION DIVISION
WICHITA, KANSAS