

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

10-25-1972  
10-25-1972  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-00272-00-00

Operator's Full Name T. W. Jackson,

Complete Address Phillipsburg, Kansas.

Lease Name Ostmeyer Well No. 1

Location NW-NW-SW Sec. 31 Twp. 6 Rge. (E) (W) 19

County Rooks Total Depth 3556'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 11:00 AM Day 23 Month 10 Year 1972

The above well was plugged as follows:

138'--8 5/8" Surface casing, cement circulated.

3545'--5 1/2" Production casing cemented on bottom with 175 Sx. Well plugged back to 3520'. Top perforations from 3357' to 3362'. Tubing packer set @ 3285' with two joints tubing "Sanded In".

Sanded well back to 3200' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (1125') and squeezed well initially with 3 sacks hulls, 20 sacks gel and 2 sacks hulls and followed with 110 Cu. Ft. cement, then 10 sacks gel and finally 75 Cu. Ft. cement. Maximum pump-in pressure-500#. Final Shut-in pressure-350#. (Mudding and cementing-operations by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. F. Nichols  
Well Plugging Supervisor

INVOICED

DATE 10/29/72  
INV. NO. 6522-W