

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20504-00-00

OCT 23 1973
10-23-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Zenith Drilling Corporation, Inc.

Complete Address 200 W. Douglas Wichita, Kansas

Lease Name Clara Miller Well No. 1

Location NE NE NE Sec. 29 Twp. 6 Rge. (E) (W) 19

County Rooks Total Depth 3605'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 1:45 A Day 20 Month 10 Year 1973

The above well was plugged as follows:

RTD 3605' 8 5/8 csg set at 208' cwc-150 sk. Cmt. Mat. 50-50 poz cmt W/6% total gel
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 190' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. J. Massey
Well Plugging Supervisor

DATE 10/23/73

INV. NO. 8041-00