

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22692-00-00  
Spot: SW Sec/Twnshp/Rge: 16-31S-11W  
1320 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: WATKINS TRUST Well #: 1-16  
County: BARBER Total Vertical Depth: 4100 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 4100 WITH 150 SX CMT  
SURF Size: 10.75 feet: 264 WITH 215 SX CMT

#133<sup>25</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/02/2005 12:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BOTTOM TO 3700' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 294' WITH 75 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER  
Date/Time Plugging Completed: 03/02/2005 1:15 PM

WitnessType: COMPLETE (100%)  
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 3700' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT W/100# HULLS. 2ND PLUG AT 294' WITH 75 SX CMT W/100# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3980	4000		
3787	3793		

RECEIVED  
MAR 07 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2647' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Stephen J. Pfeifer*  
TECHNICIAN

INVOICED  
DATE 3.7.05  
WV. NO. 2005061247

Form CP-3