

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25373-00-00
Spot: NWNENWSE Sec/Twnshp/Rge: 17-11S-20W
2409 feet from S Section Line, 1805 feet from E Section Line
Lease Name: KING Well #: 1
County: ELLIS Total Vertical Depth: 3746 feet

Operator License No.: 33491
Op Name: KING, RODNEY L.
Address: 696 D FAIRGROUND RD.
ELLIS, KS 67637

SURF Size: 8.625 feet: 233 150 SX CMT

12175

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/17/2004 8:00 AM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: DARREL ANDERSON Company: ANDERSON, C. D. DBA ANDERSON Phone: _____

Proposed Plugging Method: 1st plug @ 3717' w/25 sacks.
2nd plug @ 1565' w/25 sacks.
3rd plug @ 820' w/100 sacks.
4th plug @ 280' w/40 sacks.
5th plug @ 40' w/ wiper plug and 10 sacks.
Rat hole - 15 sacks.

Plugging Proposal Received By: DAVID WANN Witness Type: NONE
Date/Time Plugging Completed: 12/17/2004 6:15 PM KCC Agent: DAVID WANN

Actual Plugging Report:

Hole reported plugged as above.
Order 215 sacks 60/40 pozmix w/ 6% gel and 1/4 lb flowcel per sack.

Perfs:

RECEIVED
MAR 23 2005
KCC WICHITA

Remarks: CEMENTED BY SWIFT

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 3.23.05

WV. NO. 2005061318