

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-20967-00-01  
Spot: NE Sec/Twnshp/Rge: 2-35S-14W  
1320 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: STERNBERGER E Well #: 1-2  
County: BARBER Total Vertical Depth: 4855 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

CIBP Size: feet: 4054 WITH 2 SX CMT  
CIBP Size: feet: 4450  
PROD Size: 4.5 feet: 4855 WITH 225 SX CMT  
SURF Size: 8.625 feet: 377 WITH 300 SX CMT

157<sup>79</sup>

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/18/2005 12:45 PM

Plug Co. License No.: 32297 Plug Co. Name: SUPERIOR SERVICING, INC.

Proposal Rcvd. from: KEITH SHAHAN Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: CIBP @ 4054' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/18/2005 1:45 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4054' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4772	4790		
4104	4108		

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 25 2005

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 3-25-05  
TEL. NO. 2005061326

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1988' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
MAR 23 2005  
KCC Dodge City

Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

INVOICED

Form CP-23