

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21507-00-00
Spot: SWSE Sec/Twnshp/Rge: 3-32S-33W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ANGELL Well #: 2-3
County: SEWARD Total Vertical Depth: 6020 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

MSCC Size: feet: 2984 WITH 650 SX CMT
PROD Size: 4.5 feet: 5885 WITH 310 SX CMT
SURF Size: 8.625 feet: 1792 WITH 800 SX CMT

\$195⁶⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/11/2005 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RANDY GASSAWAY Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 300# HULLS WITH 25 SX CMT. MUD SPACER TO 1800'. 150 SX CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2005 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 300# HULLS WITH 20 SX CMT. PUMP 55 BBL MUD SPACER TO 1800'. PUMP 85 SX CMT TO SURFACE. PRESSURE TO 500 PSIG & SHUT IN. BACKSIDE PRESSURED IMMEDIATELY. BACKSIDE FULL.

Perfs:

Top	Bot	Thru	Comments
5804	5808		

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 25 2005
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
MAR 17 2005
KCC Dodge City

Signed Jim Holland PART # _____
(TECHNICIAN)

INVOICED
DATE 3-25-05
NO. 2005061326

Form CP-23
[Signature]