

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-21, 955-00-00

NEENSE, Sec. 30, T 6 S, R 20W

2310 feet from ~~40~~ section line

330 FL feet from ~~40~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7076

Lease Name Nichol Well # 1

Operator: Black Diamond Oil, Inc.  
Name & Address 217 E. 32nd, Hays, Ks. 67601

County Rochester

Well Total Depth 3760 feet \$122.20

Conductor Pipe: Size ~~8 5/8"~~ feet 248'

Surface Casing: Size 8 5/8" feet 248'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 622

Address P.O. Box 506, Russell, Ks. 67665

Company to plug at: Hour: 6:30 PM Day: 22 Month: 2 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Ron Burton

(company name) Emphasis Oil Operations (phone) \_\_\_\_\_

were: Order 180 lbs. 50% permix - 4% lcl. - 3% lcl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3750' w/ 20 lbs. 2nd plug C 1860' w/ 20 lbs. 3rd plug C 1500' w/ 30 lbs. 4th plug C 320' w/ 40 lbs. 5th plug - solid bridge of shells & plug C 40' w/ 10 lbs. Circulate 10 lbs in rat hole.

Signed Patricia L. Schul  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 6:30 PM Day: 22 Month: 2 Year: 19 83

ACTUAL PLUGGING REPORT 8 5/8" - 248' casing w/ 150 lbs. cement - 2% lcl. - 3% lcl. U.

Ordered 180 lbs. 50% permix - 4% lcl. - 3% lcl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3750' w/ 20 lbs. 2nd plug C 1860' w/ 20 lbs. 3rd plug C 1500' w/ 30 lbs. 4th plug C 320' w/ 40 lbs. 5th plug - solid bridge of shells & plug C 40' w/ 10 lbs. Circulated 10 lbs in rat hole.

Remarks: Drilled in to airbrake

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 14 1983  
CONSERVATION DIVISION  
Wichita, Kansas  
3-1483

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~ (did not) observe this plugging.

INVOICED

DATE 4-4-83

INV. NO. 3842-W

Signed Patricia L. Schul  
(TECHNICIAN)