

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21802-00-00  
Spot: SWSEW Sec/Twnshp/Rge: 19-8S-22W  
2310 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: QUINT B Well #: 2  
County: GRAHAM Total Vertical Depth: 3640 feet

Operator License No.: 6139  
Op Name: BOYER, JAY C.  
Address: PO BOX 511  
HAYS, KS 67601

PROD Size: 4.5 feet: 3632 175 SX CMT  
SURF Size: 8.625 feet: 212 150 SX CMT

*# 118 30*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/22/2005 9:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: HAROLD BELLERIVE Company: BOYER, JAY C. Phone: (785) 625-3556

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Fluid 180' from surface.  
Run tubing to plug.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/22/2005 5:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 2 3/8" tubing to 2418'.  
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls.  
Lost circulation. Pulled tubing to 1760'.  
Allied pumped 90 sxs cement with 200# hulls. Cement circulated.  
PTOH. Squeezed with 30 sxs cement.  
Max. P.S.I. 500#. S.I.P. 400#.  
Hooked up to backside and pumped 80 sxs cement.  
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3591	3594		
3572	3574		
3558	3560		

RECEIVED  
MAR 07 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

*100*

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 3.8.05

INV. NO. 2005061246

FEB 28 2005

BAKER OIL OPERATIONS

DRAWER B

#2 "B" QUINT

19-8-22W  
SW SE NW


PLAINVILLE, KS 67663

CONTR RANGER DRLG. CO., INC.

CTY GRAHAM

GEOLOGICAL JAMES DILLIE

FIELD HILL CITY EAST



ELV 2154 KB SPD 5/31/83 CARD ISSUED 8/25/83

IP P 55 BO & 5 BWPD  
LKC 3558-3591 OA

2149 GL  
API 15-065-21,802

LOG	Tops .....	Depth/Datum
TOP	.....	3144- 990
HEEB	.....	3362-1208
TOR	.....	3385-1231
LKC	.....	3400-1246
BKC	.....	3614-1460
RTD	.....	3640-1486

8 5/8 " 212 / 150 SX; 4 1/2 " 3632 / 175 SX  
NO DST'S  
MCT - CO, PF (KC I) AT 3558, (KC J) AT 3572, (KC K) AT 3591,  
AC 10,000 G (28%), SWB DWN, REC 600' FL (80% OIL) / 5 HRS,  
POP, P 55 BO & 5 BWPD

COPYRIGHT 1983  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

3/27/83  
3/27/83

530101

3748  
3748